



BLOCK & PAVER SYSTEMS

CONCRETE BLOCK / BRICK PLANTS

Automated concrete block, brick and paver production systems using controlled vibration, hydraulics, mould handling and auxiliary equipment.

3/4/6/8

BLOCK

machine variants cited

SERVO

VIBRATION

controlled compaction

QUICK

MOULD CHANGE

production flexibility

Engineering overview

Automated concrete block, brick and paver production systems using controlled vibration, hydraulics, mould handling and auxiliary equipment.

Key capabilities

- Servo vibration compaction
- Hydraulic control systems
- Facemix capability
- Quick mould-change concept
- Automated pallet and cubing auxiliaries



Concrete Block / Brick Plants

Illustrative source asset

Source basis: Buildmate Concrete Block Plants page and published brochure library

Technical notes

01 Machine architecture

The current Buildmate source describes servo vibration, advanced hydraulics, optional facemix capability and quick mould change.

02 Automation and handling

Auxiliary equipment can include pallet cleaning, oiling, stacking, cubing and handling, supporting a more automated production flow.

Verified source basis: Buildmate Concrete Block Plants page and published brochure library

Technical notes

03 Paver production

Buildmate also describes paver plants using vertical mould vibration to suit paver production requirements.

04 Project configuration

Final plant configuration depends on product geometry, output targets, raw materials, mould strategy, curing and site-handling requirements.

Verified source basis: Buildmate Concrete Block Plants page and published brochure library

Project discussion

Share the target product, required output, raw-material route, site location and project stage for a technical discussion.

BUILDMATE PROJECTS PVT LTD

Sy No. 60,61,62, Gundlapochampally Village, Medchal Road, Hyderabad - 500014, Telangana, India | mvr@buildmate.in | marketing@buildmate.in | +91 7675989961 / 11

This edition uses source-grounded Buildmate information. Project-specific specifications remain subject to engineering confirmation.